

Material Schedule - Job 79336

Client	BREE CONSTRUCTION	JOB	BREE RESIDENCE
ADDRESS		ADDRESS	3 LONG ROAD
		DATE	CHRISTCHURCH
			30/11/2016
			BREE CONSTRUCTION

Description	SKU Number	Qty	Unit	Rate
STEEL				
Steel Reinforcg Deformed Rnd Bar 10mmx6m FOR STARTERS		14	Lgth	
Steel Reinforcg Deformed Rnd Bar 12mmx6m BOND BEAM		23	Lgth	
Steel Reinforcg Deformed Rnd Bar 12mmx6m FOOTINGS		28	Lgth	
Steel Reinforcg Deformed Rnd Bar 12mmx6m FOR STARTERS		6	Lgth	
Black Annealed Tie Wire 230mm 1 Kg Bndle ACCESSORIES		1	each	
FOUNDATION HARDWARE				
Hurricane Reinforcing Bar Chair 75/90 ea CHAIRS		20	each	
Novaflo 110mm p/mtr 400.110 WATER PROOFING		6.7	mtr	
Novaflo 110mm p/mtr 400.110 BLOCK ACCSRS		19.5	mtr	
Alkathene Pipe 50mm (cut)		2.0	mtr	
Bidim A19 m2 WATER PROOFING		5.4	sqm	
Bidim A19 m2 BLOCK ACCSRS		36.8	sqm	
L/lok Header Block Btm Plate Anchor each BOTTOM PLATE		10	each	
Sika Blackseal 20l WATER PROOFING		1	pail	
Sika Blackseal 20l BLOCK ACCSRS		1	pail	
Silt Fence Woven 1m x 50m		1	Roll	
Ramset Concrete Nail 75mm 100pk CF675 BOTTOM PLATE		1	box	
CONCRETE				
Structural Concrete 17.5MPa 19mm FOOTINGS		10.8	m3	
Block Grout 17.5MPa 7mm FOR GROUTING		3.5	m3	
GAP 65 Metal AGGREGATE		22.0	m3	
MASONRY				
Cement Pacific 40kg bag AGGREGATE		3	bag	
Block Pallets SUPPLY		5	each	
20.12 Block 200mm Lintel/Half End Close FOOTINGS		8	each	
20.12 Block 200mm Lintel/Half End Close WALLS		11	each	
20.15 Block 200mm Bond Beam Cnr FOOTINGS		8	each	
20.15 Block 200mm Bond Beam Cnr WALLS		52	each	
20.16 Block 200mm Bond Beam Open End FOOTINGS		48	each	
20.16 Block 200mm Bond Beam Open End WALLS		328	each	
Sand Washed Mixed Bulk AGGREGATE		0.7	m3	
Cemplus Plasticiser 1l AGGREGATE		1	each	
Sika Blackseal 20l WATER PROOFING		1	pail	
Block Cartage per Pallet		5	each	

SUBFLOOR FRAMING							
90x45 mm Rad SG8 H1.2 MG KD F/JOISTS	6.4	mtr					
90x45 mm Rad SG8 H1.2 MG KD TRIM	3.6	mtr					
140x45 mm Rad SG8 H1.2 MG KD F/JOISTS	261.7	mtr					
140x45 mm Rad SG8 H1.2 MG KD WALL PLATE	9.9	mtr					
SUBFLOOR HARDWARE							
Ecoply Flooring CD UT 2700x1200x19mm FLOORING	30	Sht					
Ecoply Flooring CD H3 CCA 2700x1200x19mm FLOORING	4	Sht					
Thermakraft Cromford Supercourse 500 150mmx20m	1	Roll					
L/lok Joist Hanger SS 47x120mm	14	each					
Sika SB Panel Adhesive 375ml 651599 FLOOR	12	each					
Washer Rnd SS M12	11	each					
Ramset SS Trubolt 12x140mm T12140SS WALL PLATE	11	each					
FRAMING HARDWARE							
Thermakraft Cromford Supercourse 500 50mmx20m W/STRAPPING	4	Roll					
Thermakraft Cromford Supercourse 500 90mmx20m W/STRAPPING	1	Roll					
Thermakraft Cromford Supercourse 500 150mmx20m BLOCK ACCSRS	1	Roll					
L/lok Strip Brace 30m w/5 Tensioners ROOF FIX	1	coil					
L/lok Wire Dog LH (Z Nail) RAFTERS	22	each					
L/lok Wire Dog RH (Z Nail) RAFTERS	22	each					
L/lok Multigrip ROOF FIX	52	each					
Atack Jamb Plate 250 box OPENINGS	3	box					
Sqr Washer Galv HD 3mm 50x50mm M12 BLOCK ACCSRS	3	each					
Chemset Stud Bolt 12x160mm CS12160 WALL PLATE	3	each					
Ramset Charge Yellow Med 100pk PLCYW22 W/STRAPPING	1	box					
Ramset Drive Pin Std Shk 75mm 100 HD875 W/STRAPPING	1	box					
Ramset Drive Pin Disc 16mm 100pk RD16 W/STRAPPING	1	box					
MIDFLOOR FRAMING							
140x45 mm Rad SG8 H1.2 MG KD F/JOISTS	7.4	mtr					
140x45 mm Rad SG8 H1.2 MG KD TRIM	4.9	mtr					
240x45 mm Rad SG8 H1.2 MG KD F/JOISTS	85.0	mtr					
240x45 mm Rad SG8 H1.2 MG KD SOLID BLOCKING	9.1	mtr					
240x45 mm Rad SG8 H1.2 MG KD TRIM	16.8	mtr					
MIDFLOOR HARDWARE							
Ecoply Flooring CD UT 2400x1200x19mm FLOORING	20	Sht					
Sika SB Panel Adhesive 375ml 651599 FLOOR	7	each					
EXTERIOR LINING							
50x25 mm Rad Merch H3.1 PG Cavity Batten CAVITY BATTEN	445.0	mtr					
50x40 mm Rad Merch H1.2 DR KD CORNERS	14.6	mtr					
Hardi RAB Hori Flash 3000mm ACCESSORIES	13	Lgth					

504 Holdfast GORILLA Foam 400ml OPENINGS	1	can		
Hardie Vent Strip 3.0m CAVITY BATTEN	22	Lgth		
Protecto Tak Primer 460g OPENINGS	6	can		
Protecto Tape 75mm x 30m CORNERS	2	Roll		
Protecto Tape 75mm x 30m OPENINGS	5	Roll		
Protecto Tape 150mm x 30m OPENINGS	2	Roll		
Protecto Detail Tape JS500 150mm x 15m OPENINGS	2	Roll		
Protecto Head Flashing Tape BT20XL 50mm x 30m OPENINGS	2	Roll		
Letterbox Scroll Top	1	each		
Hills Foldaline Prewired LT FD85028	1	each		
Sika PEF Rod 10mm p/mtr 850010 OPENINGS	109.9	mtr		
Selleys Wet Seal 270G OPENINGS	6	can		
Hardiflex RAB Sheet 6mm 2400x1200mm SH CLADDING	52	Sht		
INSULATION				
Installed Pink FG Batts R2.6 Ultra Wall WALLS	159.7	sqm		
Installed Pink FG Batts R2.6 Ceiling FLOOR	3.4	sqm		
Installed Pink FG Batts R3.2 Ceiling CEILING	21.2	sqm		
Installed Pink FG Batts R4.0 Ultra Ceiling CEILING	72.2	sqm		
Installed Pink FG Batts R4.0 Ultra Ceiling FLOOR	48.3	sqm		
Installed Pink Batts Silencer 100mm WALLS	66.7	sqm		
INTERIOR DOORS				
Cartage to Site	1	load		
2400H 410 810 MDF 30mm F/J REB JAMBS 100mm	6	each		
2400H 410 810 MDF DOOR WITH STEEL INSERT IN CAVITY SLIDER UNIT	3	each		
2400H 860 910 MDF DOOR WITH STEEL INSERT IN CAVITY SLIDER UNIT	1	each		
INTERIOR LININGS				
45x45 mm Rad SG8 H1.2 MG KD W/STRAPPING	14.4	mtr		
70x45 mm Rad SG8 H1.2 MG KD PACKING	6.3	mtr		
50x25 mm Rad Merch H1.2 DR KD W/STRAPPING	46.5	mtr		
No8 Mould Rad FJ 40mm Bev Cornice SCOTIA	171.3	mtr		
No20 Mould Rad FJ 60x10mm Sgl Bev Archtrv SKIRTING	138.6	mtr		
Gib Board Standard 10.0mm WALLS	304.1	sqm		
Gib Board Standard 13.0mm CEILING	149.8	sqm		
Gib Aqualine 10.0mm WALLS	41.3	sqm		
Gib Aqualine 13.0mm CEILING	11.6	sqm		
Rondo 16mm Furring Channel 4800mm 308 METAL C/BATTEN	58	Lgth		
Rondo 32 x 32 Perimeter Angle 3000mm NZ18 METAL C/BATTEN	56	Lgth		
Gib Fix One Adhesive 375ml CEIL ACCSRS	14	each		
Gib Fix One Adhesive 375ml WALL ACCSRS	29	each		
Dimond Gib Slim Angle Ext 2.4m 90deg ACCESSORIES	16	Lgth		
Dimond Gib Slim Angle Ext 2.4m 90deg C/BEAM	10	Lgth		

Dimond Gib Slim Angle Ext 2.7m 90deg ACCESSORIES	2	Lgth		
Dimond Gib Slim Angle Ext 3.0m 90deg ACCESSORIES	6	Lgth		
Hatch Ceiling Manhole Complete 635x535mm	1	each		
Meter Box 400x600mm	1	each		
Sika Silaflex RTV Clear 375ml	3	each		
INTERIOR HARDWARE				
Lane Cavity Slider Passage PB 332	2	each		
Lane Cavity Slider Privacy PB 333	2	each		
Lane Endeavour Bed/Bathr Set PB PT5130	1	each		
Lane Endeavour Entrance Lock SSS PT5000	1	each		
Lane Endeavour Passage Set PB PT5182	5	each		
Pryda Door Stop White p/ea DWLS	7	each		
DECK FRAMING				
140x70 mm Rad SG8 H3.2 MG Wet WALL PLATE	13.5	mtr		
90x45 mm Rad SG8 H1.2 MG KD PACKING	5.9	mtr		
90x45 mm Rad SG8 H1.2 MG KD SHEET NOGS	40.9	mtr		
90x45 mm Rad SG8 H1.2 MG KD UB PLATE	35.0	mtr		
140x45 mm Rad SG8 H1.2 MG KD D/JOISTS	61.3	mtr		
140x45 mm Rad SG8 H1.2 MG KD UB PLATE	23.4	mtr		
140x45 mm Rad SG8 H1.2 MG KD WALL PLATE	11.7	mtr		
100x25 mm Kwila Deck DECKING	889.5	mtr		
140x45 mm Rad SG8 H3.2 MG Wet D/JOISTS	205.7	mtr		
140x45 mm Rad SG8 H3.2 MG Wet SOLID BLOCKING	13.5	mtr		
140x45 mm Rad SG8 H3.2 MG Wet TRIM	36.0	mtr		
140x45 mm Rad SG8 H3.2 MG Wet WALL PLATE	14.8	mtr		
70x35 mm Rad SG8 H3.2 MG Wet FURRING	61.3	mtr		
45x45 mm Rad SG8 H3.2 MG Dry GUTTER FRAME	15.1	mtr		
70x70 mm Rad SG8 H3.2 MG Dry PACKING	13.5	mtr		
DECK HARDWARE				
No37 Mould H3 Rad Clears 18mm Angle Fillet ANGLE FILLET	31.7	mtr		
Constn Ply 5Ply H3.2 CD 2400x1200x17mm DECKING	9	Sht		
Polyfoam EPS S Polystyrene 2400x1200x 25mm	6	Sht		
L/lok Joist Hanger Double Dip 47x120mm	56	each		
Coach Bolt and Nut Galv 120mm M12 WALL PLATE	21	each		
Sqr Washer Galv HD 3mm 50x50mm M12 WALL PLATE DECK	12	each		
Sqr Washer Galv HD 3mm 50x50mm M12	21	each		
Sqr Washer SS HD 3mm 50x50mm M12 WALL PLATE DECK	23	each		
Coach Screw Galv 120mm M12 WALL PLATE DECK	12	each		
Coach Screw SS 250mm M12 WALL PLATE DECK	23	each		
NAILS				
Nail Brght Steel Jolt Hd 75x3.15mm 5kg	4	pkt		

Nail Brght Steel Jolt Hd 100x4.00mm 5kg	2	pkt		
Nail Brght Steel Flat Hd 100x4.00mm 5kg	4	pkt		
Nail SS T316 AG Timber Deck 75x3.15mm 5kg	5	box		
Nail Galv Steel Flat Hd 100x4.00mm 5kg	3	box		
Nail SS Steel Jolt Hd 100x4.00mm 5kg	2	box		
Nail Galv FH Hardiflex 40x2.80mm 5kg	1	ctn		
L/Lok Nail Galv Pan Hd 30x3.15mm 500g	17	pkt		
L/Lok Nail SS Pan Hd 30x3.15mm 500g	3	pkt		
L/lok Unique 80mmx10g Pozi drive CSK screw 250bo	1	box		
Gib Coll Screw H/Thrd 32x6 1000pk WALL ACCSRS	3	box		
Gib Coll Screw S/Tap 25x6 1000pk MCB FIXING	2	box		
Screw SS S/Tap Csk Pozi 1*1/2x8g 1000pk WALL ACCSRS	1	box		
Screw SS S/Tap Csk Pozi 1*1/2x8g 1000pk	1	box		
Ramset Concrete Nail 75mm 100pk CF675	2	box		
Ramset Concrete Nail 100mm 100pk CF699	1	box		
Screw S/Tap Csk Pozi SS 1*1/2x10g 200pk	3	pkt		
Impulse BradandFuel Pack C50 ZB20591	1	each		
Impulse NailandFuel Pk 65 Galv Rng ZB20568	2	each		
Impulse NailandFuel Pk 90 ZB20550V	2	each		
MISCELLANEOUS				
Default Owner Selected Entry Door	1	each		
Velux FCM Low Pitch Fixed Skylight 3030 895x895	1	each		
HPM D645/2 Smoke Alarm	3	each		
RETAINING WALL				
Cement Pacific 40kg bag AGGREGATE	2	bag		
Structural Concrete 17.5MPa 19mm FOOTINGS	4.5	m3		
Block Grout 17.5MPa 7mm FOR GROUTING	1.7	m3		
Block Pallets SUPPLY	3	each		
20.12 Block 200mm Lintel/Half End Close WALLS	30	each		
20.15 Block 200mm Bond Beam Cnr WALLS	30	each		
20.16 Block 200mm Bond Beam Open End WALLS	199	each		
GAP 65 Metal AGGREGATE	11.5	m3		
Sand Washed Mixed Bulk AGGREGATE	0.4	m3		
Cemplus Plasticiser 1l AGGREGATE	1	each		
Novaflo 110mm p/mtr 400.110 WATER PROOFING	7.3	mtr		
Bidim A19 m2 WATER PROOFING	22.1	sqm		
Black Annealed Tie Wire 230mm 1 Kg Bndle ACCESSORIES	1	each		
Sika Blackseal 20l WATER PROOFING	2	pail		

This job has no tags defined.

#79336 · BOH · QS: Steve (Central) · Origin: Central · 320m² · Grade: G - CA · ONE OFF CHRISTCHURCH BREE 123

Created: 30 Nov 2016 15:19:06 by Steve · Modified: 30 Nov 2016 15:21:28 by Steve